

# Generation Interconnection Request System Impact Study Report

## For Queue Project Q11-0027

Taber 345 kV  
February 24, 2013

### **1. Introduction**

This System Impact Study report documents the results of the analyses performed for interconnection request Q11-0027. The Interconnection Customer proposes a 588.7 MW natural gas combined cycle facility interconnecting at the Taber 345 kV substation in the Maryland area. The request was received on April 20, 2011. The study evaluated system intact and single contingency conditions using the regional planning case, including 22 higher-queued active requests and their assigned network upgrades.

### **2. Summary of Results**

The study did not identify any facilities overloaded as a result of the project. Network upgrade cost: \$0.  
Estimated network upgrade cost: \$0

### **3. Network Impacts**

#### **3.1 Generator Deliverability and Single Contingency Analysis**

No overloads identified.

#### **3.2 Multiple Facility Contingency Analysis**

No additional overloads were identified for multiple facility contingencies.

#### **3.3 Short Circuit and Stability**

Short circuit and stability analyses identified no additional network upgrades.

### **4. Required Network Upgrades and Cost Estimates**

None. Total network upgrade cost allocated to this project: \$0.

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.