

Generation Interconnection System Impact Study Report

For Queue Project Q12-0097

Combee Road 230 kV

March 31, 2014

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q12-0097. The Interconnection Customer proposes a 405.2 MW wind facility interconnecting at the Combee Road 230 kV substation in the Ohio area. The request was received on January 20, 2012. The study evaluated system intact and single contingency conditions using the regional planning case, including 64 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$685,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

1. Facility: Airline – Omni-Hackberry 230 kV
Contingency: Airline – Decorative Panels Intl 230 kV line
Loading: 102.7% (Rating: 445 MVA)
DFAX: 9.8%
Pre-project loading: 93.8%

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Airline – Omni-Hackberry Substation 230 kV	Reconductor line	\$4,709,000	14% (\$685,000)
	Total allocated to project		\$685,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.