

Revised Generation Interconnection System Impact Study Report

For Queue Project Q12-0130

Pinal West 138 kV
June 28, 2014

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q12-0130. The Interconnection Customer proposes a 97.5 MW natural gas combined cycle facility interconnecting at the Pinal West 138 kV substation in the Maryland area. The request was received on May 13, 2012. The study evaluated system intact and single contingency conditions using the regional planning case, including 86 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$46,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Easton 2 – Navy Mole 138.0 kV	Easton 2 – Cady 345.0 kV	104.6	342	21.4

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Easton 2 – Navy Mole 138.0 kV	Reconductor line	\$290,000	16% (\$46,000)
	Total allocated to project		\$46,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.