

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q13-0283

University 230 kV
May 23, 2015

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q13-0283. The Interconnection Customer proposes a 54.9 MW solar photovoltaic facility interconnecting at the University 230 kV substation in the Indiana area. The request was received on November 05, 2013. The study evaluated system intact and single contingency conditions using the regional planning case, including 173 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$134,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

For the loss of COOK - FLOOD ST 500kV line, the FLOOD STREET - UNIVERSITY 230kV line loads to 107.4% of its 1,190 MVA rating. Project DFAX: 32.0%.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
FLOOD STREET - UNIVERSITY 230kV line	Reconductor line	\$7,102,000	2% (\$134,000)
	Total allocated to project		\$134,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.