

Generation Interconnection System Impact Study Report

For Queue Project Q14-0382

State Street 230 kV

November 18, 2015

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q14-0382. The Interconnection Customer proposes a 347.7 MW natural gas combined cycle facility interconnecting at the State Street 230 kV substation in the Indiana area. The request was received on September 21, 2014. The study evaluated system intact and single contingency conditions using the regional planning case, including 229 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$925,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Swan Vly 500 kV/230 kV Transformer Bank: 109.6% loading (1,041 MVA) following the outage of the Trego to Swan Vly 500 KV; DFAX = 5.5%.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Swan Vly 500 kV/230 kV Transformer Bank	Replace transformer with higher-rated unit	\$21,103,000	4% (\$925,000)
	Total allocated to project		\$925,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.