

Revised Generation Interconnection System Impact Study Report

For Queue Project Q15-0514

Homer 138 kV
July 24, 2017

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q15-0514. The Interconnection Customer proposes a 152.3 MW wind facility interconnecting at the Homer 138 kV substation in the Pennsylvania area. The request was received on September 03, 2015. The study evaluated system intact and single contingency conditions using the regional planning case, including 205 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The study did not identify any facilities overloaded as a result of the project. Network upgrade cost: \$0.
Estimated network upgrade cost: \$0

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

No overloads identified.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

None. Total network upgrade cost allocated to this project: \$0.

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.