

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q16-0566

Palo Duro 230 kV
September 29, 2017

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q16-0566. The Interconnection Customer proposes a 173.0 MW battery energy storage facility interconnecting at the Palo Duro 230 kV substation in the Ohio area. The request was received on January 04, 2016. The study evaluated system intact and single contingency conditions using the regional planning case, including 230 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$2,963,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Dismal Riv - Becker 345 KV Line	Fishkill Plains - Dillard-Orange 345 KV	105.2	1,250	6.3

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Dismal Riv - Becker 345 KV	Reconductor line	\$80,911,000	4% (\$2,963,000)
	Total allocated to project		\$2,963,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.