

Generation Interconnection System Impact Study Report

For Queue Project Q16-0592

Pagosa 138 kV

March 28, 2017

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q16-0592. The Interconnection Customer proposes a 72.4 MW solar photovoltaic facility interconnecting at the Pagosa 138 kV substation in the New Jersey area. The request was received on March 03, 2016. The study evaluated system intact and single contingency conditions using the regional planning case, including 307 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$340,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Jones Chapel Substation 500/230 kV Autotransformer	Dekalb / Jones Chapel 500 kV L	101.3	1,337	5.7

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Jones Chapel 500-230 kV Transformer	Replace transformer with higher-rated unit	\$32,301,000	1% (\$340,000)
	Total allocated to project		\$340,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.