

Revised Load Interconnection System Impact Study Report

For Queue Project Q16-0662

Blue Ravine-School 230 kV
October 22, 2017

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q16-0662. The Interconnection Customer proposes a 237.9 MW large load (data center) facility interconnecting at the Blue Ravine-School 230 kV substation in the Indiana area. The request was received on August 13, 2016. The study evaluated system intact and single contingency conditions using the regional planning case, including 303 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The study did not identify any facilities overloaded as a result of the project. Network upgrade cost: \$0.
Estimated network upgrade cost: \$0

3. Network Impacts

3.1 Load Deliverability Analysis

No overloads identified.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

None. Total network upgrade cost allocated to this project: \$0.

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.