

# **Generation Interconnection Combined Feasibility / System Impact Study Report**

## **For Queue Project Q17-0822**

Beback 138 kV  
February 02, 2019

### ***1. Introduction***

This System Impact Study report documents the results of the analyses performed for interconnection request Q17-0822. The Interconnection Customer proposes a 121.1 MW wind facility interconnecting at the Beback 138 kV substation in the Pennsylvania area. The request was received on July 06, 2017. The study evaluated system intact and single contingency conditions using the regional planning case, including 303 higher-queued active requests and their assigned network upgrades.

### ***2. Summary of Results***

No thermal overloads attributable to this project were identified. No network upgrades are required.  
Estimated network upgrade cost: \$0

### ***3. Network Impacts***

#### ***3.1 Generator Deliverability and Single Contingency Analysis***

No overloads identified.

#### ***3.2 Multiple Facility Contingency Analysis***

No additional overloads were identified for multiple facility contingencies.

#### ***3.3 Short Circuit and Stability***

Short circuit and stability analyses identified no additional network upgrades.

### ***4. Required Network Upgrades and Cost Estimates***

None. Total network upgrade cost allocated to this project: \$0.

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.