

Revised Generation Interconnection System Impact Study Report

For Queue Project Q17-0855

Recovery Soco 138 kV
June 22, 2019

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q17-0855. The Interconnection Customer proposes a 141.3 MW solar photovoltaic facility interconnecting at the Recovery Soco 138 kV substation in the Maryland area. The request was received on August 29, 2017. The study evaluated system intact and single contingency conditions using the regional planning case, including 281 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

No thermal overloads attributable to this project were identified. No network upgrades are required. Estimated network upgrade cost: \$0

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

No overloads identified.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

None. Total network upgrade cost allocated to this project: \$0.

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.