

Generation Interconnection Request System Impact Study Report

For Queue Project Q17-0888

Taber 345 kV
March 27, 2019

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q17-0888. The Interconnection Customer proposes a 1225.5 MW natural gas combined cycle facility interconnecting at the Taber 345 kV substation in the Maryland area. The request was received on October 31, 2017. The study evaluated system intact and single contingency conditions using the regional planning case, including 342 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$1,297,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Mccall Substaion Substation - Stillwater Hydro Electric Project 138 KV line	Taber - Dixleta 345 KV	101.1	224	5.1

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Mccall Substaion Substation - Stillwater Hydro Electric Project 138 KV line	Reconductor line	\$1,297,000	100% (\$1,297,000)
	Total allocated to project		\$1,297,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.