

Revised Generation Interconnection System Impact Study Report

For Queue Project Q18-1014

James St 100 kV
March 23, 2020

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q18-1014. The Interconnection Customer proposes a 155.7 MW natural gas combined cycle facility interconnecting at the James St 100 kV substation in the Illinois area. The request was received on June 22, 2018. The study evaluated system intact and single contingency conditions using the regional planning case, including 306 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$94,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monfort – Wabash 230.0 kV: 101.2% loading (1,056 MVA) following the outage of the Richland – Dekalb 500.0 kV; DFAX = 18.0%.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Monfort – Wabash 230.0 kV	Reconductor line	\$8,226,000	1% (\$94,000)
	Total allocated to project		\$94,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.