

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q18-1115

New Hollandale 138 kV
October 19, 2020

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q18-1115. The Interconnection Customer proposes a 98.2 MW wind facility interconnecting at the New Hollandale 138 kV substation in the Ohio area. The request was received on November 25, 2018. The study evaluated system intact and single contingency conditions using the regional planning case, including 312 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$247,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

For the loss of Redford - New Hollandale 138.0 kV line, the Hopson - Sienna 100.0 kV line loads to 112.3% of its 126 MVA rating. Project DFAX: 11.1%.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Sienna - Hopson 100.0 kV	Rebuild line with higher-capacity conductor	\$2,167,000	11% (\$247,000)
	Total allocated to project		\$247,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.