

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q19-1287

Scott 138 kV
September 29, 2020

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q19-1287. The Interconnection Customer proposes a 184.5 MW solar plus storage facility interconnecting at the Scott 138 kV substation in the Pennsylvania area. The request was received on September 11, 2019. The study evaluated system intact and single contingency conditions using the regional planning case, including 485 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$9,819,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Walnut Crk-Volcano 138.0 kV Line	Coronet-Ft Humbug 500.0 kV	266.9	240	7.7

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Volcano-Walnut Crk 138.0 kV	Rebuild line with higher-capacity conductor	\$9,819,000	100% (\$9,819,000)
	Total allocated to project		\$9,819,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.