

Generation Interconnection Request System Impact Study Report

For Queue Project Q19-1311

Bayport Sw Sta 230 kV
December 18, 2020

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q19-1311. The Interconnection Customer proposes a 117.0 MW solar photovoltaic facility interconnecting at the Bayport Sw Sta 230 kV substation in the Ohio area. The request was received on October 12, 2019. The study evaluated system intact and single contingency conditions using the regional planning case, including 466 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$3,418,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Lawrence Energy Center - Barna 100kV	Rouse - Bayport Sw Sta 230kV L	104.1	143	7.4

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Lawrence Energy Center - Barna 100kV	Reconductor line	\$3,418,000	100% (\$3,418,000)
	Total allocated to project		\$3,418,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.