

Revised Generation Interconnection System Impact Study Report

For Queue Project Q20-1484

Rogers Lake 230 kV
April 01, 2022

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q20-1484. The Interconnection Customer proposes a 186.4 MW solar photovoltaic facility interconnecting at the Rogers Lake 230 kV substation in the Ohio area. The request was received on May 31, 2020. The study evaluated system intact and single contingency conditions using the regional planning case, including 410 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$4,411,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Rogers Lake 138/1kV Autotransformer: 132.7% loading (131 MVA) following the outage of the Gilstrap to Rogers Lake 230 kV; DFAX = 100.0%.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Rogers Lake 138/1kV Autotransformer	Replace transformer with higher-rated unit	\$4,411,000	100% (\$4,411,000)
	Total allocated to project		\$4,411,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.