

Revised Generation Interconnection System Impact Study Report

For Queue Project Q20-1522

East Drainage Canal 230 kV
August 21, 2022

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q20-1522. The Interconnection Customer proposes a 185.3 MW solar plus storage facility interconnecting at the East Drainage Canal 230 kV substation in the Ohio area. The request was received on July 10, 2020. The study evaluated system intact and single contingency conditions using the regional planning case, including 360 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$8,553,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
EAST DRAINAGE CANAL - LENKURT 100 kV line	JAMES DE YOUNG - ST. LAWRENCE SUBSTATION 230 kV line	122.0	134	12.8

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
EAST DRAINAGE CANAL - LENKURT 100 kV line	Rebuild line with higher-capacity conductor	\$8,553,000	100% (\$8,553,000)
	Total allocated to project		\$8,553,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.