

Generation Interconnection Request System Impact Study Report

For Queue Project Q20-1604

Escondido 138 kV
September 17, 2022

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q20-1604. The Interconnection Customer proposes a 76.4 MW wind facility interconnecting at the Escondido 138 kV substation in the New Jersey area. The request was received on October 31, 2020. The study evaluated system intact and single contingency conditions using the regional planning case, including 411 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$54,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Agate Beach Ss 108-Corson Station 138.0 kV	Agate Beach Ss 108-Lacassine Substation 345.0 kV	111.5	222	6.3

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Agate Beach Ss 108-Corson Station 138.0 kV	Rebuild line with higher-capacity conductor	\$1,797,000	3% (\$54,000)
	Total allocated to project		\$54,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.