

Revised Generation Interconnection System Impact Study Report

For Queue Project Q21-1776

North Bay 230 kV
October 15, 2022

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q21-1776. The Interconnection Customer proposes a 96.9 MW solar photovoltaic facility interconnecting at the North Bay 230 kV substation in the Ohio area. The request was received on June 09, 2021. The study evaluated system intact and single contingency conditions using the regional planning case, including 545 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$999,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

1. Facility: Portage Lakes to Weedpatch Substation 230.0 kV L
Contingency: W Canton to Pt Arena Substation 500.0 kV
Loading: 107.8% (Rating: 875 MVA)
DFAX: 18.0%
Pre-project loading: 105.8%

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Weedpatch to Portage Lakes 230.0 kV	Reconductor line	\$9,148,000	11% (\$999,000)
	Total allocated to project		\$999,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.