

Generation Interconnection System Impact Study Report

For Queue Project Q21-1801

Blue Ravine-School 230 kV

March 23, 2023

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q21-1801. The Interconnection Customer proposes a 87.1 MW battery energy storage facility interconnecting at the Blue Ravine-School 230 kV substation in the Indiana area. The request was received on June 29, 2021. The study evaluated system intact and single contingency conditions using the regional planning case, including 484 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

No thermal overloads attributable to this project were identified. No network upgrades are required. Estimated network upgrade cost: \$0

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

No overloads identified.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

None. Total network upgrade cost allocated to this project: \$0.

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.