

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q21-1828

Robison Park 230 kV
September 02, 2023

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q21-1828. The Interconnection Customer proposes a 133.5 MW battery energy storage facility interconnecting at the Robison Park 230 kV substation in the Indiana area. The request was received on July 24, 2021. The study evaluated system intact and single contingency conditions using the regional planning case, including 421 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The study did not identify any facilities overloaded as a result of the project. Network upgrade cost: \$0.
Estimated network upgrade cost: \$0

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

No overloads identified.

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

None. Total network upgrade cost allocated to this project: \$0.

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.