

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q21-1851

Airline 230 kV
July 21, 2023

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q21-1851. The Interconnection Customer proposes a 277.3 MW solar photovoltaic facility interconnecting at the Airline 230 kV substation in the Ohio area. The request was received on August 06, 2021. The study evaluated system intact and single contingency conditions using the regional planning case, including 455 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$902,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Kean Mtn And Grassy Crk / Barr Lake 345 KV	Antelope Vly Station / Hinton Ap 138 KV	104.0	1,240	5.1

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Kean Mtn And Grassy Crk / Barr Lake 345 KV	Reconductor line	\$28,970,000	3% (\$902,000)
	Total allocated to project		\$902,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.