

Generation Interconnection Request System Impact Study Report

For Queue Project Q21-1911

Barcola 345 kV
February 02, 2023

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q21-1911. The Interconnection Customer proposes a 126.3 MW solar photovoltaic facility interconnecting at the Barcola 345 kV substation in the West Virginia area. The request was received on October 18, 2021. The study evaluated system intact and single contingency conditions using the regional planning case, including 620 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$120,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
FOX HILLS-WHATSHAN 138 kV	BARCOLA-BRIDGEVILLE 345 kV	103.3	222	15.1

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
WHATSHAN-FOX HILLS SUBSTATION 138 kV Line	Reconductor line	\$1,677,000	7% (\$120,000)
	Total allocated to project		\$120,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.