

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q22-2006

Monfort 100 kV
September 19, 2023

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q22-2006. The Interconnection Customer proposes a 51.2 MW solar photovoltaic facility interconnecting at the Monfort 100 kV substation in the Indiana area. The request was received on February 15, 2022. The study evaluated system intact and single contingency conditions using the regional planning case, including 561 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$36,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
ZONA LIBRE 6007 / GEORGE NEAL S 230 KV Line	SWAN VLY / TREGO 500 KV	100.3	2,154	7.2

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
ZONA LIBRE 6007 / GEORGE NEAL S 230 KV Line	Reconductor line	\$7,482,000	0% (\$36,000)
	Total allocated to project		\$36,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.