

Generation Interconnection Request System Impact Study Report

For Queue Project Q22-2010

Feedville 138 kV
July 16, 2023

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q22-2010. The Interconnection Customer proposes a 87.5 MW solar photovoltaic facility interconnecting at the Feedville 138 kV substation in the Maryland area. The request was received on February 17, 2022. The study evaluated system intact and single contingency conditions using the regional planning case, including 591 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$2,041,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
Watford City / Toledo 138kV L	Morgan Falls Substation / Toledo Substation 138kV	100.8	176	7.2

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Watford City / Toledo Substation 138kV	Reconductor line	\$4,354,000	47% (\$2,041,000)
	Total allocated to project		\$2,041,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.