

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q22-2065

Hat Rapids 138 kV
August 30, 2023

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q22-2065. The Interconnection Customer proposes a 50.3 MW battery energy storage facility interconnecting at the Hat Rapids 138 kV substation in the Virginia area. The request was received on April 14, 2022. The study evaluated system intact and single contingency conditions using the regional planning case, including 622 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$911,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

Monitored Facility	Contingency	Loading (%)	Rating (MVA)	DFAX (%)
York Canyon – Binary 138kV	New Denver – Martin Dam 138kV	103.0	215	9.6

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
York Canyon – Binary 138kV	Reconductor line	\$8,771,000	10% (\$911,000)
	Total allocated to project		\$911,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.