

Generation Interconnection System Impact Study Report

For Queue Project Q22-2149

Scooteney 138 kV

July 30, 2023

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q22-2149. The Interconnection Customer proposes a 133.4 MW solar plus storage facility interconnecting at the Scooteney 138 kV substation in the Kentucky area. The request was received on August 04, 2022. The study evaluated system intact and single contingency conditions using the regional planning case, including 718 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$1,985,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

1. Facility: SCOOTENEY - SHINGLETON 138 KV
Contingency: COLINE RD - BRUNNER ISLAND 500 KV Line
Loading: 104.5% (Rating: 253 MVA)
DFAX: 100.0%
Pre-project loading: 51.8%

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
SCOOTENEY - SHINGLETON 138 KV	Reconductor line	\$1,985,000	100% (\$1,985,000)
	Total allocated to project		\$1,985,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.