

Generation Interconnection Combined Feasibility / System Impact Study Report

For Queue Project Q23-2282

Beaver Brook 138 kV
July 23, 2024

1. Introduction

This System Impact Study report documents the results of the analyses performed for interconnection request Q23-2282. The Interconnection Customer proposes a 47.3 MW battery energy storage facility interconnecting at the Beaver Brook 138 kV substation in the New Jersey area. The request was received on January 24, 2023. The study evaluated system intact and single contingency conditions using the regional planning case, including 581 higher-queued active requests and their assigned network upgrades.

2. Summary of Results

The project was found to contribute (DFAX of 5% or greater) to 1 overloaded facility. The total estimated cost of the network upgrades allocated to this project is \$65,000.

3. Network Impacts

3.1 Generator Deliverability and Single Contingency Analysis

1. Facility: Paul Sweet - Altadena 138kV
Contingency: Deptford - Thorofare 138kV
Loading: 114.5% (Rating: 172 MVA)
DFAX: 7.2%
Pre-project loading: 112.5%

3.2 Multiple Facility Contingency Analysis

No additional overloads were identified for multiple facility contingencies.

3.3 Short Circuit and Stability

Short circuit and stability analyses identified no additional network upgrades.

4. Required Network Upgrades and Cost Estimates

Facility	Required Upgrade	Cost Estimate	Allocation to Project
Paul Sweet - Altadena 138kV	Rebuild line with higher-capacity conductor	\$970,000	7% (\$65,000)
	Total allocated to project		\$65,000

This report is a simulated study produced by the gridconstraint research prototype on a public synthetic-but-realistic PJM-footprint case; it is not a PJM document.